

CENTRAL POWER RESEARCH INSTITUTE

Switchgear Testing & Development Station

Govindpura, Bhopal- 23

SUPPLEMENTARY TEST LABORATORY

PROVISIONAL TEST REPORT

Test Report No. & Date : 2013/STL/1732 **21 NOV 2013**

Customer his reference and address : M/s Carrier Airconditioning & Refrigeration Ltd.,
Narsingpur, Kherki Daula Post,
Gurgaon-122 004.

Manufacturer, his reference & address : M/s Khokhar Electricals Pvt. Ltd.,
6/2-2, Kirti Nagar Industrial Area,
New Delhi-15.

Particulars of apparatus tested : 400 V, 265 A, 30XA, Electrical
Control Box

Designation : Nil

Type : Nil

Identification No./Sample code No. : STDSSL13S1258

Sl.No. : Nil

Drawing No. (under revision) : GA530XA(IP-44) sheet 1 of 2 & 2 of 2

Date (s) of test (s) : 20.11.2013

No.of samples tested : One

Test conducted : Degree of Protection IP-44

Particulars of test conducted : The above test was conducted on the sample as per standard. The wire of specified diameter did not enter inside the main enclosure after IP-4X test and no traces of water observed inside the sample after IP-X4 test.

Test in accordance with standard/ specifications : IS/IEC: 60947-1, 2004

Customer's requirement/deviations if any : Nil

Name of the Witnessing person

Customer's representative : Mr. Sanjeev Garg, Manager

Other than Customer's representative : Mr.Rajinder Singh, G.M


TEST ENGINEER


JOINT DIRECTOR
संयुक्त निदेशक
Joint Director

Note:

- This is only a provisional report. The final test report along with drawings and other documents will be issued separately.
- The results are not binding on the testing authority until the final test report is issued.
- Corrections/erasing invalidate the test report.

Central Power Research Institute
स्विचगियर परीक्षण तथा विकास केन्द्र
Switchgear Testing & Development
गोविन्दपुरा भोपाल - 462023
Govindpura Bhopal 462 023